

Minden-Gardnerville Sanitation District

GENERAL NOTES:

1. THE CONTRACTOR SHALL CONDUCT A PRECONSTRUCTION MEETING WITH AN MGSD REPRESENTATIVE PRESENT.
2. CONTRACTOR SHALL CONTACT AND COORDINATE WITH MGSD AND ALL OTHER UTILITIES 48 HOURS PRIOR TO CONSTRUCTION. ALL CONSTRUCTION SHALL CONFORM TO MGSD STANDARDS AND NO BACKFILLING WILL BE ALLOWED UNTIL INSPECTED AND APPROVED BY MGSD.
3. NEW SEWER LINES SHALL BE TESTED IN ACCORDANCE WITH THE MGSD ORDINANCE AND REQUIRED AIR TEST FOR ACCEPTANCE SHALL BE CONDUCTED AFTER ALL OTHER UTILITIES ARE INSTALLED.
4. ALL SANITARY SEWER LINES SHALL BE PVC SDR35. ALL SANITARY SEWER SERVICES SHALL BE 4" PVC SDR35 UNLESS OTHERWISE NOTED.
5. AN "S" SHALL BE STAMPED OR CHISELED IN THE CONCRETE CURB WHERE THE LATERAL CROSSES UNDER IT FROM THE MAIN.
6. UPON COMPLETION OF IMPROVEMENTS, REPRODUCIBLE RECORD DRAWINGS SHALL BE SUBMITTED TO MGSD AND APPROVED BY THE MGSD BOARD.
7. MGSD SHALL BE NOTIFIED PRIOR TO POURING CONCRETE COLLARS ON MANHOLE INSTALLATIONS.